



VCCX Components

2425 South Yukon Ave - Tulsa, Oklahoma 74107-2728 - Ph. (918) 583-2266 Fax (918) 583-6094
AAONEcat32 Ver. 4.259 (SN: 6114768-)

1A 1B 1C 1D 2 3 4 5A 5B 5C 6A 6B 6C 7 8 9 10 11 12 13 14A 14B 15 16 17 18 19 20 21 22 23

RN - 011 - 4 - 0 - EA09 - 3F9 : A000 - D00 - DCD - 0BA - 00EAHB3 - 00 - 00A0H00VB

Tag: 9 Ton Suite (3000sqft)

Job Name: *Urbandale - JLR*

Job Number: *Job #470*

VCCX For:

VCCX Date: *July 26, 2017*

Hardware Included For VCCX Controller

Part #	Included Parts	Assigned Channel	BACnet Point
V87900	VCCX CONTROLLER		
P94320	Space Temp Sensor	VCCX control point AI 1	AI:12
V13050	OSA Temp/Hum Sensor	EBUS2 communicating sensor	AI:16,AI:17,AI:18,AI:19
P94320	Space Temp Slide Adjust	VCCX control point AI 2	AI:8
R82890	Supply Temp Sensor - Field Installed	VCCX control point AI 3	AI:9
	Supply Fan Control Signal 0-10VDC	VCCX control point AO 1	AI:22
	Economizer	VCCX control point AO 2	AI:30
R62330	Proof of Air Flow	VCCX control point BI 1	BI:6
R64580	Dirty Filter Sensor	VCCX control point BI 2	BI:25
	Safety Shut Down	VCCX control point BI 8	BI:26
	Supply Fan	Configured Relay point	BI:63
V61520	DIGITAL REFRIGERATION MODULE		
R57800	Comp Discharge Temp A	RSMD point AI5	AI:56
V38391	Suction Pressure Sensor A	RSMD point AI1	AI:48
V38410	Discharge Pressure Sensor A	RSMD point AI2	AI:50
V38410	Discharge Pressure Sensor B	RSMD point AI4	AI:55
R63950	Modulated Condenser Signal B	RSMD point AO2	AI:44
R63950	Modulated Condenser Signal A	RSMD point AO1	BI:
	Comp Status Input A	RSMD point BI1	
	Comp Status Input B	RSMD point BI2	BI:79
	Emergency Shutdown	RSMD point BI4	BI:81,82
	Condenser Enable AB	RSMD Fixed Relay point	BI:78,BI:85
	Comp Enable A	RSMD Fixed Relay point	AI:46
	Comp Enable B	RSMD Fixed Relay point	BI:77,BI:84
	Condenser Enable B	RSMD Fixed Relay point	BI:86
V12090	MODULATING GAS MODULE		
	ModGas Gas Valve Signal	MODGAS-X	
	ModGas High Speed Enable	MODGAS-X	AI:43
	ModGas Low Speed Enable	MODGAS-X	